BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/05/2014-15 Dated: 11-12-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 14

Name of Work:-Maintenance of BBMP office buildings in ward no:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H S PALAKSHAMURTHY	
				Rate	Rate in Words
1	KSRB 2-1.1 : Earth work in surface excavation in **Ordinary soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road, drains and trenches of pipes lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m excavated surface levelled and neatly dressed earth to be levelled after breaking of clods and neatly dressed as per specifications specification No KBS 2.1(a) / 2.3.1 **PWD SR 2014-15 (P.5 / 2.1)**	Cum	456.95	144.16	Rupees one hundred forty four and paise sixteen only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix **1:4:8** using 4**0mm** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 **PWD SR 2014-15 (P.12/4.3)**	Cum	21.30	4500.00	Rupees four thousand five hundred only
3	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 **PWD SR 2014-15 (P.23/5.5)**	Cum	10.94	3700.00	Rupees three thousand seven hundred only
4	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in **basement** with **cement mortar 1:6**, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification. KBS 5.1.13 **(P.23/5.9) PWD SR 2014-15**	Cum	2.84	4458.36	Rupees four thousand four hundred fifty eight and paise thirty six only
5	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. **Page No. 109/ Item No. 15.3 / PWD SR 2014-15**	sqm	14.35	110.00	Rupees one hundred ten only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H S PALAKSHAMURTHY	
				Rate	Rate in Words
6	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix **1:2:4** with cement @240kgs with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation plinth and cills, including cost of all materials labour, HOM of machineries curing complete asper specification.	sqm	7.80	5228.98	Rupees five thousand two hundred twenty eight and paise ninety eight only
7	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with **20mm (M20)** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for ground floor level for roof slabs, starecase, lintel, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, coping, bed struts, buttersses, string or lacing courses, parapets, coping, bed blocks, plain window cils, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No.KBS 4.1, 4.6 **(P.No.13/4.11) PWD SR 2014-15**	Cum	24.96	5600.00	Rupees five thousand six hundred only
8	KSRB 4.9.2 : Providing T.M.T Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required , tying with binding wire and anchoring to the adjoining memebers wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **PWD SR 2014-15(P.NO17/4.46)**	Qtl.	22.46	7905.60	Rupees seven thousand nine hundred five and paise sixty only
9	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	169.00	292.68	Rupees two hundred ninety two and paise sixty eight only
10	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, No. 6/ Item No. 2.10/ PWD SR 2014-15	Cum	456.95	116.60	Rupees one hundred sixteen and paise sixty only
11	applying and fixing M.S Rectangular poles made but of equal angles of 65x65x6mm welded together and fixed inCC(1:2:4) with 2 Nos 16mm dia M.S hold fast rods each of length 25cms including cost of all materials, cutting, bending scafolding.	Rmtr	28.80	1093.92	Rupees one thousand ninety three and paise ninety two only
12	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at tip and bottm as required including cost of all materials,	sqm	30.00	563.92	Rupees five hundred sixty three and paise ninety two only only
13	Providing and fixing M.S Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S rectangular poles) and spot welding the chain link with M.S block pipe including.	Rmtr	40.00	316.94	Rupees three hundred sixteen and paise ninety four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H S PALAKSHAMURTHY	
				Rate	Rate in Words
14	KSRB 7.1 providing and fixing inposition collapsable steelshutters withsingerdoubeleaf with vertical channe 120mmx10mmx20mmx5mm size , with iron and bottom rails of iron sections of 40x40x6mm with 38mm dia steel pulleys complete with bolt and nuts, pulleys complete with bolt and nuts locking arrangements, stopers, handles on borht side with 7.5cms opeings at 10cms C to c applying a priming coat of red lead paint cost of material, labour HOM of machinery complete as per specifications.	sqm	5.76	4581.32	Rupees four thousand five hundred eighty one and paise thirty two only
15	KSRB 7.9 providing and fixing M.S gro;; wok for withdown and vertilators weigting 21kg/sqm using M.S Flats of MS squar roads, or combination of MS flats and quare roads as per approved design drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of material, fixtures labour and HOM of machinery complete as per specifications.	Kg's	315.00	98.58	Rupees ninety eight and paise fifty eight only
16	KSRB 15-16.1 Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	sqm	221.14	57.24	Rupees fifty seven and paise twenty four only
	G.F		211.05	60.24	Rupees sixty and paise twenty four only
	S.G		375.92	63.24	Rupees sixty three and paise twenty four only
17	KSRB 15-17-6 providing and applying painting two coats (excluding priming coat) on new wood surface and /or wood based surface with enamel paint to give an even shade, clening the surface of all sirt, dust and foreign matter sand papering including cost of materials, labouyr, complete as per specifications.	Sqm	186.97	82.68	Rupees eighty two and paise sixty eight only
	G.F		110.57	85.68	Rupees eighty five and paise sixty eight only
	S.G		55.28	88.68	Rupees eighty eight and paise sixty eight only
18	Providing and fixing precast RCC slabs as per approved design , specification and Direction Engineer-in charge (Approved Data Rate)		45.00	1245.00	Rupees one thousand two hundred forty five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.